

**EVALUATION REPORT**  
**(As Per Rule 35 of PP Rules. 2004)**

1. **Name of Procuring Agency** : Cantonment Board Malir
2. **Method of Procurement** : Single-Stage-Two Envelope 36(b) of the PPRA rules
3. **Title of Procurement** : Cleaning & de-silting of manholes, sewer lines of different diameters& Nallahs / Storm Water Drains
4. **Tender Inquiry No** : Daily "Nai Baat Karachi", daily "Express Tribune Karachi" dated 27.05.2023.
5. **PPRA Ref. No.(TSE)** : TS511743E dated 26.05.2023
6. **Date & time of Bid Closing** : 13.06.2023 at 1230 hrs
7. **Date & time of Bid Opening** : 13.06.2023 at 0100 hrs
8. **No of Bid Received** : Total 03 Nos.
9. **Criteria for Bid Evaluation** : Lowest quoted units rates in Rs.
10. **Detail of Bid(s) Evaluation** : Given Below

S. #	Description	Sewerage Line Dia	M/s S.T & Sons	M/s Shah Faisal & Brothers
			Rate Per Rft In Rs.	
1.	Cleaning inside sewerage lines completely restoring original silt free space / diameter of pipe line by labour and equipment (Mechanically/Electrically driven). Including accessories like pulley's steel rope buckets and draggers sizing from 6" to 18" dia. Their "to and fro" pulling action (No of passes shall be as many as required) would be taken two phases (First phase entire length from down stream to up stream) bringing down peak hours sewerage to flow inside pipe line (as free flow) and in second phase from up stream to down stream of entire length ensure no silt is observed in buckets (6" dia to 18" dia) except only sewage water. The job includes all the hire / cost of equipment and accessories of above winching machine / devices along with / engines with winching drum set having steel rope pulley mounted over it, steel bucket fro 6" to 18" dia hooks and other protection like safety barriers, traffic signs, traffic cones ensuring no damage to pipe along with ensuring safety to labour and other public property lives and removal silts/solid during de-silting and clearance of site etc complete as per fully satisfaction of the CEO/CCE.	12"	200	245
		15"	235	265
		18"	320	395
		24"	475	495
		36"	520	600
2.	Cleaning / desilting of rain / storm water drain (20' to 30' wide) passing through CBM limits from Gulshan-e-Rahim, including removal of obnoxious vegetations along sides to achieve unobstructed natural / gradient flow approximately length 6.5 KM		Rate per Mtr In Rs.	Rate per Mtr In Rs.
			6200	6700

  
Cantonment Executive Officer  
Malir Cantonment

Copy to:-

1. Account Branch.
2. IT Branch for Publication on PPRA website.
3. Mater file.