



PAKISTAN TELEVISION CORPORATION LIMITED

TENDER INVITING NOTICE

Ref. No. ENCL/PLG/18-272/24207

Subject: **TENDER FOR CONSTRUCTION OF (COLLAPSED BOUNDARY WALL & CIVIL WORKS) AT PTV REBROADCAST STATIONS DAROSH, PANDU & THUB.**

M/s. Pakistan Television Corporation Limited invites sealed tenders through e-Pak Acquisition & Disposal System (EPADS) <https://eprocure.gov.pk> as well as manual on the subject cited above. Interested parties may download the tenders' documents from PTV and PPRA websites. Price tenders (single stage two envelope bidding procedure) as per PPRA Rule (36 - B). PEC Registered Category (C-5) or above having Codes BC04-CE01-CE09-CE10-CE11.

Sealed quotations should be addressed to **Controller Audit Chairman Senior Tender Committee**, Federal TV Complex, Constitution Avenue, Islamabad and must reach in the office on or before **12th June, 2024 at 11:00 am**. For any further information, please contact with undersigned. PTV reserves the right to reject all bids or proposals and grounds of rejection will be communicated to the parties if requested, but there will be no binding on PTV to justify those grounds.

TERMS AND CONDITIONS:

- Interested bidders must be registered themselves on the (EPADS) <https://eprocure.gov.pk/#/supplier/registration> and submit their tender documents accordingly through EPADS as well as manual.
- **Single Stage-Two Envelops:** the bids shall comprise of single package containing two separate envelops. Each envelop shall be contain separately the financial proposal and the technical proposal. Envelops shall be marked as "**FINANCIAL PROPOSAL**" and "**TECHNICAL PROPOSAL**" in bold and legible letters. Disclosure of financial proposal at the time of technical bid opening will lead to disqualification.
- Closing date of submission is **12th June, 2024 by 11:30 am**. The Technical bid shall be opened half hour after the closing time in the presence of the bidders who wish to be present at PTV Headquarters Office, F-5/1, Islamabad.
- The constructor shall also submit its financial status by providing the audit reports for the last three years.
- The earnest money in the shape of Bank Draft / Cash Deposit receipt (CDR) from a schedule bank in Pakistan in the favour of **PTVC**, equal to **Rs. 170,000/-** should be submitted at aforementioned address which will be refundable.
- Tenders received after due date and time will not be entertained.
- Only technical qualified bidders will be invited to participate in the opening of financial bidding.
- Quotation / tender validity period ((120) days.
- Manual overwriting will lead to rejection of bid.
- Full name of firm, address alongwith tool. Machinery staff etc.
- NO litigation certificate on stamp paper (original)
- Last 06 month Bank statement required.
- Rates should be quoted in Pak Rs. for whole Projects (Pandu, Thub & Darosh)

The contractor shall liable to complete the work and shall not

- a. Leave work as incomplete.
 - b. Sublet or subcontract the assigned work.
- There should be no overwriting and /or cutting in the quotation. Similarly, lead pencil must not be used for writing.
 - Job must be started within 15 days and completed within 45 days from the award of Contract / Work Order.
 - Transportation charges whatsoever will be borne by the party to whom job will be awarded.
 - In case of any dispute, only court of Jurisdiction at Islamabad / Rawalpindi shall have jurisdiction to decide the matter.

(SAGHEER-UD-DIN)
Assistant Controller Engineering Civil
Room No. 201, 2nd Floor, Block No. II,
PTV-Headquarters Office, Islamabad.
Ph. No. 051-9077326

PAKISTAN TELEVISION CORPORATION LIMITED

BOQ / COST ESTIMATE OF BOUNDARY WALL AT RBS-DAROSH

SR. NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Excavation in all kind of soil including Shingle, Gravelly, Clay or Mud conglomiration of gravel are Boulders, Soft, Sandy or Dis-intigrated Sandy, of Hard Rock etc., including Staking of Serviceable Materials sepraty and back filling the excavated suitable material in Foundation Plinth or under floor Cutting / Blasting if required Breaking Clods, watering consolidation by ramming in layers dressing and disposal of surplus excavated stuff as directed.	4176	Cft		
2	Providing and laying PCC 1:4:8 using Ordinary Portland Cement and 3/4" crushed aggregate with local approved Sand including leveling compacting and curing etc. complete in all respects.	200	Cft		
3	Providing Fabricating and laying Steel reinforcement bar of 40,000 PSI yield strength including the cost of Straightening, Cutting, Bending, Binding, Wastage Rolling, margin and such over laps not shown on Drawing placing in position on MS Chairs and Annealed Steel Wire complete in all respects.	2500	KG		
4	Providing and laying reinforced cement concrete 1:2:4 using Ordinary Portland Cement and 3/4" crushed aggregate with local approved Sand including leveling compacting and curing etc. complete in all respects.	680	Cft		
5	Providing and laying Rubble Randon Stone Masonry Work in Wall Foundation & Plinth laid in 1:3 Cement Sand Mortar including Racking out Joints and Curing complete in all respects in and Height / Floor.	550	Cft		
6	Providing and laying PCC Block Masnory 1:3:6 Masonry in superstructure laid in 1:3 Cement Sand Mortar including Racking out Joints and Curing complete in all respects in and Height / Floor.	1000	Cft		
7	Providing Cement Sand Plaster 1:4 in superstructure 1/2" thick including curing complete in all respects in any Height / Floor.	2500	Sft		
8	Providing Cement Sand Pointing 1:3 in superstructure 1/2" thick including curing complete in all respects in any Height / Floor.	1000	Sft		
	Total				

G.S.T. 16%

Total Rs =

PAKISTAN TELEVISION CORPORATION LIMITED

**COST ESTIMATE FOR CONSTRUCTION OF POL / OIL STORE
AT RBS-PANDU (AJK)**

SR. NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	OIL ROOM Excavation any kind of soil upto 2' depth and back filling with excavated suitable material in foundation plinth or under floor as per site requirements.	735	Cft		
2	Providing and laying PCC 1:4:8 in foundation including compacting and curing etc. complete in all respects.	40	Cft		
3	Providing and Laying Structure Concrete RCC 1:2:4 using O.P. Cement, 50% Lawrencepur Sand, 50% Local River Sand Margala Crush and of 3000 psi cylinder strength at 28 days including Formwork and its removal, Curing complete in respects.	950	Cft		
4	STONE MASONRY Providing and Laying stone masonry Walls laid in 1:5 Cement Sand Mortar in below plinth, complete in all respects.	250	Cft		
5	PLASTER WORK Supply, Make, apply and Cure 13mm (0.5") thick Internal and 3/4" External smooth finished 1:3 Cement Sand Plaster as per specifications, complete in all respects.	1100	Sft		
6	FLOORING Providing and Laying PCC 1:2:4 for Floor Work as per Specifications, complete in all respects.	168	Sft		
7	WATER PROOFING Providing and Laying 2" thick Terrazo in Panal and required Slope as per Specifications, complete in all respects.	168	Sft		
8	RAIN WATER TROUGHS Providing and Laying Rain Water Troughs 2' x 2' using non-structure Cement Concrete 1:2:4 and finish with 10mm thick 1:3 Gray Cement and Plaster with PVC 4" Dia Pipe etc. as per Specifications, complete in all respects.	1	Job		

9	STEEL GATE (Type SD1 6'-0" x 9'-0") (POL / OIL Store) Provide and Fix in Position Steel Hinged Fully Louvered double Leaf Door in 16 Gauge M.S Sheet and 1-1/2 x 1-1/2 x 1/4" MS Angle Iron Frame and 1/4" MS Flate Plate Welded together form Z Section Steel Frame including Paint and all Hardware Work, complete in respects.	1	Job		
10	STEEL GATE (Type SD1 7'-0" x 9'-0") (BUNKER) Provide and Fix in Position Steel Hinged Fully Louvered double Leaf Door in 16 Gauge M.S Sheet and 1-1/2 x 1-1/2 x 1/4" MS Angle Iron Frame and 1/4" MS Flate Plate Welded together form Z Section Steel Frame including Paint and all Hardware Work, complete in respects.	1	Job		
11	PAINT WORK Providing and Applying Distempering Paint (ICI Dulux or Equal) to Internal surface of approved color and shade upto any height, complete in all respects.	600	Sft		
12	Reinforcement Steel Bars of Grade 60 (min 60,000 psi yield strength) including Bending, Cutting and Placing, complete in all respects.	800	KG		
					16% GST
					TOTAL COST
					Rs.

PAKISTAN TELEVISION CORPORATION LIMITED
CONSTRUCTION OF BOUNDARY WALL (FENCE) AT RBS THUB
 Ref No. ENG/PLG/B-303

SR. NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1.	Providing and fixing un-climbable Security Fence 10' height from NSL with using material such as MS Angle Iron L Shape 3" x 3" x 1/4" including Barbed Wire 10' height with 6" C/C horizontally and 8" C/C vertically. Excavation for Foundation size 1' x 1', including 6" PCC using ratio 1:4:8 & PCC 1:2:4 in foundation size 1' x 1' x 3'. 2 coats of Red Exide Enamel Paint to Angle Iron complete as per drawings and design and as directed by the Engineer including labor charges complete in all respects.	878	Rft		
					Add 16 % GST
					Rs.
					Total
					Rs.