

**PAKISTAN TELEVISION CORPORATION LIMITED**  
**PTV SPORTS, ISLAMABAD**  
**Tel: +92-51- 9265346-42**

July 9, 2024

Ref. No. PTV-Sports/Admin/Purchase/1000

1. PTV WEBSITE
2. E-PADS/PPRA
3. 02 Newspaper (01 Urdu & 01 English)


**TENDER NOTICE**

Pakistan Television Corporation Limited Sports/ (PTV Drama & Film Academy), Islamabad invites tender from well reputed GST/income Tax registered firms/vender who are on active taxpayer list of the Federal Board of Revenue and having E-PADS registration for the Construction of Sports Complex.

**TERMS & CONDITIONS**

1. The bidders/tenders must submit bids/proposal according to 36-A on EPADS on **24.07.2024** and the quotations will be opened at 11:30 am on same.
2. All prices must be quoted in local currency, inclusive of all applicable taxes such as GST, Income Tax and Custom & Excise duties etc, otherwise it will be assumed that the price included all the taxes.
3. PTV will not be responsible for and cost due to changes in tax rate by the Local or Provincial or Federal Government of Pakistan at any time.
4. Payment shall not be made in advance.
5. The payment will only be made on provision of Annexure "C" by the concerned suppliers /firms.
6. All Bids must be accompanied by an earnest money/bid security (refundable) of Rs. 267383.00 in the form of Pay Order or Demand Draft in the name of PTV Sports, Personal cheque /cash is not acceptable.
7. The bid without earnest money will not be entertained.
8. Tender's rates must be valid for a period of 60 days from the date of opening.
9. PTV reserves the right to reject any or all the bids as per PPRA Rule 33.
10. On acceptance of quotations supplies will be taken in one lot and not piece meal on the date as given on the purchase order.
11. NO EXTENSION of time will be allowed.
12. **TENDER DOCUMENTS CAN BE RECEIVED FROM THE OFFICE OF UNDERSIGNED OR DOWNLOAD FROM PPRA, EPADS & PTV WEBSITE.**

Yours faithfully,

  
**(JAVEED IQBAL)**  
Admin & Personnel Manager

**TENDER PAPERS**  
**FOR CONSTRUCTION OF CRICKET PITCH & BADMINTON GROUND FOR PTV**  
**ACADEMY, ISLAMABAD**

S.No	Description	Qty	Unit
1	Structure excavation in soil (except rock) above sub soil water level for other structure and unsuitable excavated material dispose off outside the PTV premises any lead as per specification. Complete in all respect as per instructed by the incharge.	2000	Cft
2	Excavation holes 2'x2'x4' in ordinary soil, provision and erection in position for pipe , including lean concrete 6" thick PCC(1:4:8) size deep RCC (1:2:4 ) 1.5'x1.5'x3.5' including back filling, compacting, curing, shuttering, leveling, scaffolding etc. as per specification. Complete in all respect as per instructed by the incharge.	20	Nos.
3	Providing and fixing 14 SWG steel pipe comprising 4" dia pipe Including welding, jointing, threading, grinding, leveling, finishing, painting upto 21' high above concrete etc. Complete in all respect with all accessories as per specification instructed by the incharge.	200	Rft
4	Providing and fixing 14 SWG steel pipe comprising 2" dia pipe Including socket, elbows, Tee, capping, welding, jointing with 4" existing pipe in horizontal, threading, grinding, leveling, finishing, painting upto 21' high above concrete etc. Complete in all respect with all accessories as per specification instructed by the Engineering Incharge.	2700	Rft
5	Providing and laying of lean concrete using crushed or broken stone graded including formwork, placing, leveling, finishing, mixing and curing and other allied work etc. as per specification. Complete in all respect as per instructed by the incharge.		
	a) PCC (1:4:8)	800	Cft
6	Provide and lay lean concrete using stone crush as coarse aggregate including compacting, formwork, placing, leveling, finishing, mixing and curing and other allied work etc. as per specification. Complete in all respect as per instructed by the incharge.		
	a) PCC (1:2:4)	1200	Cft
7	Providing and laying, 20mm thick Terrazzo floor using marble chips (1:2) with ordinary cement, including marble patti as required, cutting and rubbing, grading, finishing as per specification. Complete in all respect as per instructed by the incharge.	660	Sft
8	Excavation holes, in ordinary soil, provision and erection in position for Street Light pole but Round conical galvanized, 6 meter long, including lean concrete 6" thick PCC (1:4:8) size 1.5'x1.5'x4' deep RCC (1:2:4) back filling "J" shape anchor dia 25mm 4' long, bolt set, single arm pole complete with base plate, ,G.I nuts, washers, all necessary materials etc. as per specification. Complete in all respect as per instructed by the incharge.	12	Nos.

9	P/F of 14 SWG frame door size 7'x3' including welding, painting, jointing, grinding, finishing, hinges, door earl with lock, covering with iron galvanized 50mm x 50mm mesh, 10 SWG and fixed with tinned tracks, G.I staples, etc as per specification. Complete in all respect as per instructed by the incharge.	21	Sft
10	Supply and fix wire netting, iron galvanized 50mm x 50mm mesh, 10 SWG and fixed welding, painting, jointing, grinding, finishing. iron galvanized 50mm x 50mm mesh, 10 SWG and fixed with tinned tracks, G.I staples, etc as per specification. Complete in all respect as per instructed by the incharge.	1800	Sft
11	Providing / fixing/laying a parachute net No.36 or 42 for catching cricket balls. High-density nylon net for durability and UV resistance. Mesh Size 1.5 2 cm, cord thickness 2-3 mm. Padding around the edges of the net. Including supporting ropes/ cable (HD), hooks required size, lightweight, foldable etc. Complete in all respect as per site requirment and instructed by the incharge.	11000	Sft
12	Supply at site, fabrication, installation, testing, commissioning and connections of wires / cables of Distribution Boards "Light / Power" concealed type to be installed made of MS sheet 16 SWG degreased and derusted, zinc phosphate, finished with electrostatic powder coating of 15 micron thickness in approved colour with hinged door, flexible earthing strap lockable handle, catcher, earthing bar, neutral strip, internal wiring from MCBs terminating on cable terminal blocks, including cost of all necessary materials complete in all respects. All DBs mentioned below shall have 3 phase indication lamps transformer type of colour Red, Yellow, Blue and 1-Voltmeter scaled 0-500 V. with Voltmeter selector switch of 7 positions. DBs shall be manufactured by any one of the manufacturers as mentioned in Annexure "A".		
	100Amps 3 pole (MCCB) circuit Breaker	1	No.
	15Amps single pole (MCCB) circuit Breaker	30	Nos.
13	Supply, installation, testing, commissioning and connections of wires / cables (PAK Cable) 16mm.sq. 2core PVC insulated 300/500 V grade wire as specified in approved colour , including cost of all necessary materials complete in all respects.		
	16mm 4core wire for main line	200	Mtr
	2.5mm 2core wire breaker to lights point	400	Mtr
14	Supply, installation, testing, commissioning of complete flood light 200 watts fitting consisting of light fixture made by Philips with all accessories including conduits and cable complete in all respects.	20	Nos.
15	Supply, installation, testing, commissioning of complete street light 100 watts fitting consisting of light fixture made by Philips with all accessories including conduits and cable complete in all respects.	12	Nos.

16	P/L 2" thick tuff pavers of concrete 7000 psi strength grouting with sand matching colour pigment including lean concrete (1:4:8), cutting, finishing, rendering, shuttering, scaffolding and curing. Complete in all respect as per specification and instructed by the incharge.	10000	Sft
17	Construction, excavation, Provide, placing & fixing of inauguration plate Engraved Granite Marble including brick masonry work base 3'x4'x5', plaster, ceramic tiles, filling, cutting, finishing, rendering, shuttering, scaffolding and curing. Complete in all respect as per specification and instructed by the incharge.	one	job
18	Construction of a outdoor Badminton Court including compacting, clearing/ grading/ grabbing of site, including lean concrete 4" thick, pouring of reinforced concrete 6", topping 20mm thick terrazzo with marble patti as required, surface finishing with approved suitable material, line marking with paint, installation of net posts and net as required, as per requirement. Complete in all respect as per specification and instructed by the incharge.	1250	Sft